

MANCUNIAN WAY FLYOVER

Location: Manchester
Client: Manchester City Council
Contractor: A F Budge Contractors Ltd
Consulting Engineer: Major Highways Consortium
Construction: 1990
EMJ Panel Value: £115,000
Status: Complete, Opened



PERMADECK FORMWORK CASE STUDY



EMJ GRP PERMADECK FORMWORK DETAILS

Panel Type: Standard Type 8
Panel Width: 838 mm
Panel Length: Various, 2100 mm
Panel Bearing: 50mm
Panel Clear Span: Various, 2000mm
Panel Rib Centres: 127 mm
Panel Height: 63mm
Total Area: 4700 m²
Concrete Deck Thickness: 275 mm
Deflections: 14 mm
Design Criteria: BA 36 90

